

Wall Types

Exterior walls 2x6 wood stud
Interior walls 2x4 wood stud, unless noted otherwise

Wall Keys

- 2 2x wood studs on the flat
- 3 2x3 wood stud wall, 16" oc
- 6 2x6 wood stud wall, 16" oc

Note: 2x4 wood stud wall, 16" oc unless otherwise noted

Key Notes

- A 30" x 22" Minimum Attic Access
Panel - Insulated (RO 34" x 26")
- F Field locate for plumbing or mechanical
- V Verify size of fixture or appliance
Adjust dimensions to accommodate
- S Snug - Door or Window trim will be snug
and may need to be cut down
- C Center - Place door or window centered
on wall
- D Double Stud or structural mull - adapt to
suit chosen window brand.
Object is to have some "bite" for curtain
hardware and exterior aesthetics.
- SD Smoke Detector
- CO Carbon Monoxide Detector

Dimensions



Dimensions are to face of stud, unless noted otherwise.
Closets are 24" clear inside, unless dimensioned otherwise.

Square Footages

- 1. Sq ft numbers are interior to room for use in calculating
finishes.
- 2. Cabinets and fixtures not subtracted.
- 3. Add for doorways when floor finishes run through.

Notes

- 1 - Exterior walls 2x6 wood stud @ 16" oc. Provide
insulation & vapor barrier conforming to state or local codes.
Interior sheathing 1/2" gypsum board. Provide 1/2" exterior
rated sheathing, house wrap with drainage plane and siding.
Provide step flashing at walls adjacent to roof planes.
- 2 - Interior walls 2x4 wood stud @ 16" oc, unless noted
otherwise.
- 3 - Roof - see structural for rafter sizes. Provide 5/8"
exterior rated roof sheathing 15# roofing felt, ice & water
shield at eaves and valleys, aluminum drip edge and
asphalt shingles or metal roofing. Structure not calculated to
support slate or tile. Flash all penetrations. Provide
cricket at any added chimneys.
- 4 - Provide roof and/or ceiling insulation per code. Provide
soffit and ridge vents where required for insulation strategy.
(Verify with code officer - closed cell spray foam or dense-
pack cellulose installed at rafters and filling ridge and eaves
generally contra-indicates venting, batt insulation always
requires venting).
- 5 - Provide smoke detectors where shown, where required
by code and where required by local authorities.
- 6 - Provide fire resistive materials where required by code,
including but not limited to, firestopping at penetrations, 1/2"
drywall on walls and 5/8" drywall on ceilings to separate
garage (where garage present in design) from dwelling, and
separation of dwellings (where more than one dwelling
present in design), and protection of flammable insulation
materials.
- 7 - Confirm bottom of window opening relative to frame.
Adjust head heights as required to conform to IRC 2009
R612.2, or provide code approved guards.
- 8 - Compliance with code requirements for rooms size and
clearance, (hallway widths, room sizes, etc) assume 1/2"
drywall on walls and 1/2" drywall on 3/4" strapping on
ceilings. Adjust as required if materials differ.
- 9 - Some windows must be installed with a head height
greater or lesser than the standard 80" or 82 1/2" to provide
clearance at kitchen counters, to meet code sill height or to
clear roofs. Where approx 84" head height is called for,
install 2x10 header tight to double top plate, frame window
RO tight to header.
- 10-Shear is only called out where Continuous Portal Frame
will not suffice. See Section R602.10.4 (Pages 173 - 179) of
the IRC 2009.



First Floor Plan

NOTE TO HOMEOWNER:
These construction plans ARE NOT a part of your construction contract with your builder,
unless your P&S agreement specifies that they are. Your P&S and it's attachments (like the
builder's specifications or a review set of this design) describes what you and your builder
agreed the builder would build for you. We here at Artform Home Plans do not have the
authority to obligate your builder to provide you with amenities like fireplaces and spa tubs.
The contract between you and your builder governs.



Dear Code Officer.

These are predesigned home plans, designed to bring good
design and construction drawings to people at more affordable
prices and faster time frames than traditional architecture. Where
traditional "internet" home plans disclaim all responsibility, we split
responsibility between us (Artform) and the owner. We encourage
the future homeowners to use a quality builder who can assist
them with this. They are responsible for thermal and moisture
decisions and for meeting coding in ways that a quality builder
should know. We are responsible for things that are directly
related to the design and/or that a quality builder couldn't
reasonably figure out on their own - specifically the following IRC
2009 code sections:

- 1 - Room sizes (Section R304)
- 2 - Ceiling Height (Section R305)
- 3 - Floor space & ceiling height at Toilet, Bath and Shower Spaces
(Section R307)
- 4 - Hallway widths (Section R311.6)
- 5 - Door types & sizes (Section R311.2)
- 6 - Floor space in front of doors (Section R311.3)
- 7 - Stair width - The stairs in our designs will be a minimum of 36"
wide measured wall surface to wall surface, allowing compliance
with R311.7.1 with installation of correct handrail.
- 8 - Stairway headroom (Section R311.7.2)
- 9 - Stair treads and risers (Section R311.7.4)
- 10 - Landings for stairways (Section R311.7.5)
- 11 - Emergency Escape Window Sizes (Section R310.1.1,
R310.1.2, R310.1.3 and R310.1.4). Casement windows may
require manufacturer's emergency escape window hardware. Will
also comply with NFPA 101.
- 12 - Structural Floor Framing (Section R502.3) Where dimensional
lumber is shown, framing members will be sized according to this
section of the code. Where engineered wood products are shown,
those framing members will be sized according to the
manufacturer's tables for loads and spans, or sizes will have been
calculating using manufacturer's published materials properties.
13 - See structural sheets for additional notes.

The builder can and should add information to this set, such as
Rescheck, a hand markup of our generic thermal and moisture
section, additional information about doors and windows (such as
fire rating, tempering, etc), foundation drops relative to site
grading, and sometimes their chosen method of basement egress.
These drawings are not intended to be used without that additional
information.

Where a construction address is shown on the drawings, it is for
copyright control only. We have not inspected the site, adapted
the design to state specific laws (except where it says so in the
drawings) or site or region specific climate conditions.
Homeowner and/or Builder shall be responsible for thermal and
moisture control strategies, materials choices and compliance with
applicable laws and ordinances.

Please do feel free to call us with any questions. We can and do
update our drawings and standard notes to address specific
concerns, especially in jurisdictions where our clients will be
building again.

Dear Everybody.

With these drawings a copyright license is granted for a single
construction only at 1 Sunningdale, Somersworth, NH by or for DWL
Builders, LLC. This is a License to Build, and does not include a
License to Modify, except as required to conform to building code or
fulfill builder's/owners responsibilities.

Permissible uses of these drawings:

- All activities associated with construction at the listed address.
- Pricing or preliminary discussions with zoning or code officials for
construction at other addresses, with prior notification to Artform
Home Plans - just use the Contact form on the web site - <http://www.artformhomeplans.com/contact.a5w>

Not Permitted:

- Application for any permits or other approvals for construction at
properties other than the listed address, including but not limited to
construction, zoning, conservation, or design review.
 - Modification of the basic design.
- Use of these drawings outside these parameters is a violation of
federal copyright law, punishable by both civil action and criminal
prosecution. It's also stealing or enabling theft, which doesn't
suddenly become less bad just because it's "intellectual property".
Making changes, even significant changes, does not change this.
Under copyright law, that's "derivative works". You still used our
work, and we still spent significant time preparing it, quite possibly
in the wee hours when everybody else was sleeping!

We can provide drawings suitable for use in obtaining design or
zoning approvals without incurring the expense of a full set of
construction drawings. Contact us for more information. We
want to allow reasonable use at reasonable costs, just not have
our work stolen.



AFHP CD Comments 14.8.X7

Your use of these drawings constitutes an acceptance of
responsibility as outlined in "Dear Code Officer" on the first
page of these drawings, and on our web site:
<http://www.artformhomeplans.com/TermsConditions.a5w>

If you have any concerns or questions, please feel free to
contact us. We are happy to clarify matters that fall within our
scope, as listed on the first page. We can also often provide
affordable support for issues that are your responsibility, such
as energy design/calcs, or additional detailing.

Artform Home Plans	
AFHP Design # 414.144 © 2008-2015 Wendy Welton 603.431.9559	
Strawberry Ranch 1 Sunningdale Somersworth, NH	
1/4"=1'-0" unless noted otherwise / Print @ 1:1 PDF created on: 10/26/2015, drawn by ACJ	Issued for Construction

Strawberry Ranch



Door & Window Notes

- Rated Doors:** Provide fire rated and/or self-closing doors where required by local codes or local authorities
- Trimmed Openings:** Trimmed openings not shown on schedule. See Plan.
- Window Tempering:** Provide tempered windows where required by local codes or local authorities. Tempering column provided here for convenience. Windows have not been reviewed for tempering requirements.
- Window RO's:** 1/4" or 1/2" on each of 4 sides allowed for window RO's, typical. Review framing size vs RO size. Adjust per manufacturer's requirements and/or builder preference.
- Egress Windows:** Provide minimum one door or window meeting egress requirements in basement, in each sleeping room, in each potential sleeping room, and other locations required by local code, in sizes required by local code. Note that casement windows coded by manufacturer as meeting IRC 2006 egress requirements typically need to be ordered with specific hardware. Emergency Escape Window Sizes (Section R310.1.1, R310.1.2, R310.1.3 and R310.1.4). Will also comply with NFPA 101.
- Basement Windows:** Add basement windows as required to meet state or local code requirements, including but not limited to egress and light/ventilation.
- Skylights:** Skylights are not shown on this schedule, but may be required. Consult builder and/or see floor plan.
- Minimum window sill height:** IRC 2006 and later requires that upper floor window sills be 24" from floor.

DOOR SCHEDULE						
NUMBER	QTY	FLOOR	SIZE	WIDTH	HEIGHT	TYPE
D01	1	0	2668 L EX	32"	80"	HINGED
D04	1	1	2668 L IN	30"	80"	HINGED
D05	2	1	2468 R IN	28"	80"	HINGED
D06	1	1	2468 L IN	28"	80"	HINGED
D07	3	1	2868 R IN	32"	80"	HINGED
D08	1	1	2868 L EX	32"	80"	HINGED
D09	4	1	2868 L IN	32"	80"	HINGED
D10	1	0	2468 R EX	28"	80"	HINGED
D11	1	1	2868 R EX	32"	80"	HINGED
D12	1	2	11028 L IN	22"	30"	HINGED
D13	1	2	11028 R EX	22"	30"	HINGED
D14	1	0	6068 R EX	72"	80"	SLIDER
D15	1	1	6068 R EX	72"	80"	SLIDER
D16	2	1	9090	108"	96"	GARAGE
D17	1	0	5468 L/R	64"	80"	4 DR. BIFOLD
D18	1	1	4268	50 3/16"	80"	MULLED UNIT
D19	2	1	4068 L/R IN	48"	80"	DOUBLE HINGED

WINDOW SCHEDULE							
NUMBER	QTY	WIDTH	HEIGHT	R/O	EGRESS	TEMPERED	DESCRIPTION
W01	1	29 1/2"	39 1/2"	30"X40"			DOUBLE HUNG
W02	3	35 1/2"	17 1/2"	36"X18"			FIXED GLASS
W03	2	38"	61 1/2"	38 1/2"X62"	YES		DOUBLE HUNG
W04	1	35 1/2"	23 1/2"	36"X24"		YES	AWNING
W05	1	77"	61 1/2"	77 1/2"X62"			2X DH
W06	3	77"	61 1/2"	77 1/2"X62"	YES		2X DH
W08	1	23 1/2"	23 1/2"	24"X24"		YES	AWNING

Your use of these drawings constitutes an acceptance of responsibility as outlined in "Dear Code Officer" on the first page of these drawings, and on our web site: <http://www.artformhomeplans.com/TermsConditions.a5w>

If you have any concerns or questions, please feel free to contact us. We are happy to clarify matters that fall within our scope, as listed on the first page. We can also often provide affordable support for issues that are your responsibility, such as energy design/calcs, or additional detailing.

Artform Home Plans

AFHP Design # 414.144
© 2008-2015 Wendy Welton 603.431.9559

Strawberry Ranch
1 Sunningdale
Somersworth, NH

1/4"=1'-0" unless noted otherwise / Print @ 1:1
PDF created on: 10/26/2015, drawn by ACJ

2
Issued for
Construction

Structural General Notes:

1. Builder shall consult and follow the building code and other regulations in effect for the building site for all construction details not shown in these drawings. Requirements described here are specific to this design and/or are provided as reference. Additional building code or local requirements may apply.
2. Builder shall maintain a safe worksite, including but not limited to, provision of temporary supports where appropriate and adherence to applicable safety standards.
3. Design is based on the snow load listed on the framing plans, 90 mph basic wind speed, Exposure type B, soil bearing capacity of 2000 psf, and Seismic Category C, unless otherwise noted on the framing plans. Builder shall promptly inform Artform Home Plans of differing conditions.

Foundations

1. No footing shall be poured on loose or unsuitable soils, in water or on frozen ground.
2. All exterior footings to conform to all applicable code requirements for frost protection.
3. All concrete shall have a minimum compressive strength of at least 3000 PSI at 28 days.
4. Foundation anchorage to comply with IRC 2009 Section R403.1.6, it shall consist of minimum size 1/2" diameter anchor bolts with 3/16" x 2" x 2" washers at a maximum of 72" oc for two stories or 48" oc for more than two stories, max of 12" from each corner, min of 2 bolts per wall. Anchor bolt shall extend 7" into concrete or grouted cells of concrete masonry units. Be aware that a garage under may be counted by your code officer as a story. Additional anchorage may be required at braced walls.

Wood Framing

1. All structural wood shall be identified by a grade mark or certificate of inspection by a recognized inspection agency.
2. Structural wood shall be Spruce-Pine-Fir (SPF) #2 or better.
3. When used, LVL or PSL indicate Laminated Veneer Lumber or Parallel Strand Lumber, respectively. Products used shall equal or exceed the strength properties for the size indicated as manufactured by TrusJoist.
4. When used, AUS indicates wood I-joists as manufactured by Boise Cascade. Products of alternate manufacturers may be substituted provided they meet or exceed the strength properties for the member specified.
5. All floor joists shall have bridging installed at mid-span or at 8'-0" oc maximum.
6. Floor systems are designed for performance with subfloor glued and screwed.
7. At posts, provide solid framing/blocking to supports below. Provide minimum 1 1/2" bearing length for all beams and headers, unless noted otherwise.
8. All wood permanently exposed to the weather, in contact with concrete or in contact with the ground shall meet code requirements for wood in these environments.
9. Deck ledgers shall be securely attached to the structure and/or independently supported, including against lateral movement, per building code requirements and best practices. Unless otherwise noted, decks shall have solid 4x4 pt posts up to 6 ft above grade, and solid 8x8 for heights above that.
10. Wherever beams are noted as Flush framed, install joist hangers at all joists, sized appropriately for the members being connected.
11. Support the lower end of roof beams via minimum 2" horizontal bearing on a post, ledger or via an appropriately sized and configured hanger.
12. Where multiple beams are supported on one post, provide min 2" bearing for each, via either appropriately sized post cap or additional post(s).
13. Hangers, post caps, ties and other connectors shall be as manufactured by Simpson Strong Tie, as designed to connect the members shown, and shall be installed per manufacturer's instructions.


Prefabricated Wood Trusses

1. Where trusses are indicated on the drawings, truss design shall be provided by truss manufacturer.
2. Trusses shall be designed in accordance with applicable provisions of the latest edition of the National Design Specifications for Wood Construction (NDS), American Forest and Paper Association (APA), and Design Specifications for Metal Plate Connected Wood Trusses (ANSI/TPI 1), Truss Plate Institute (TPI) and code of jurisdiction.
3. Manufacturer shall furnish design drawings bearing seal and

Foundation Contractor Check List


Confirm or review the following prior to forming & pouring foundation

- Initials Date Checked
- | | |
|-------|---|
| _____ | Confirmed soil bearing |
| _____ | Checked w/GC for added foundation steps to suit grade |
| _____ | Confirm sill plate thickness (foundation bolts to extend through all) |
| _____ | Confirmed garage door size |
| _____ | Checked w/GC for added basement windows |
| _____ | Checked w/GC for added basement man doors |
| _____ | Confirmed sizes & locations mech/plbg penetrations |
| _____ | Confirmed sizes and locations of beams w/GC, added or adjusted beam pockets |
| _____ | Confirmed location and installed electrical service grounding - See GC for location |





Typical Basement Post

Not to Scale



Foundation Plan

Structure designed for
Snow Load of 60 psf



Beam Pocket

Scale 1/2"=1'-0"

TYPICAL PERIMETER FOUNDATION WALL:

- 8" poured concrete, 8 ft forms, min 7'-10" finished, with total of 3 rebar, as follows:
 - (1) #4 rebar, 4" from top
 - (1) #4 rebar @ vertical midpoint. Omit this rebar at walls 4 ft high or less.
 - (1) #4 rebar, min 3" from bottom or per code
 - Lap corners & splices of rebar per code.
- Secure sill to foundation with 1/2" diameter anchor bolts that extend 7" into concrete and tightened with a nut and washer @ 6' oc & max 12" from each corner & each end @ wood sill splices - if built-up sill, bolts must extend through all sill plates or straps must secure all sill plates.

TYPICAL PERIMETER FOOTING:

1. Verify that depth of home matches chart. Depth is foundation dimension eave to eave. Contact Artform Home Plans if you believe the chart does not match the plan.
2. Select column for snow load shown on the structural plans.
3. Select soil bearing pressure based on soil type and/or consultation with code officer.
4. The required footing size is at the intersection of the Snow Load and Soil PSI. Rebar is not required. Key or pin foundation wall to footing per code. For the purposes of permitting, soil bearing for New England is assumed to be 2,000 PSI.
FAQ - Adding rebar to footings does not reduce the required width. Rebar affects performance with earth movement, like an earthquake and has near zero effect on bearing capacity.

Guide to Soil PSI

3,000	Sandy gravel and/or gravel (GW and GP)
2,000	Sand, silty sand, clayey sand, silty gravel and clayey gravel (SW, SP, SM, SC, GM and GC)
1,500	Clay, sandy clay, silty clay, clayey silt, silt and sandy silt (CL, ML, MH and CH)

Footing Size Type 8.8.28		up to 28 ft plan depth 8 ft nominal basement height 8" foundation wall Full basement plus 2 stories				
		Snow Load				
Soil PSI		50	60	70	80	
		3,000	16" x 8"	16" x 8"	16" x 8"	16" x 8"
		2,000	18" x 8"	18" x 8"	18" x 8"	20" x 8"
		1,500	22" x 8"	22" x 8"	24" x 8"	24" x 8"


Footing Size Type 8.8.36		33-36 ft plan depth 8 ft nominal basement height 8" foundation wall Full basement plus 2 stories				
		Snow Load				
Soil PSI		50	60	70	80	
		3,000	16" x 8"	16" x 8"	16" x 8"	16" x 8"
		2,000	20" x 8"	20" x 8"	22" x 8"	24" x 8"
		1,500	26" x 8"	28" x 8"	30" x 8"	30" x 8"

Your use of these drawings constitutes an acceptance of responsibility as outlined in "Dear Code Officer" on the first page of these drawings, and on our web site:
<http://www.artformhomeplans.com/TermsConditions.a5w>


If you have any concerns or questions, please feel free to contact us. We are happy to clarify matters that fall within our scope, as listed on the first page. We can also often provide affordable support for issues that are your responsibility, such as energy design/calcs, or additional detailing.

10/26/2015 2:35:26 PM

\\AFDIS\STATION\AFA Staff\Access-Home Design\Bery Charming Ranches & Cranches\Strawberry Ranch - 6 Sunningdale layout




Front Elevation




Porch Column Detail


Note: Dimensions are approximate, builder may exercise some latitude



Rear Elevation




Right Elevation




Left Elevation

Your use of these drawings constitutes an acceptance of responsibility as outlined in "Dear Code Officer" on the first page of these drawings, and on our web site: <http://www.artformhomeplans.com/TermsConditions.a5w>

If you have any concerns or questions, please feel free to contact us. We are happy to clarify matters that fall within our scope, as listed on the first page. We can also often provide affordable support for issues that are your responsibility, such as energy design/calcs, or additional detailing.




1- Cross Section @ Bedrooms




2- Cross Section @ Stair (Upper)



for construction only at:
1 Sunningdale, Somersworth, NH
by or for DWL Builders, LLC



3- Cross Section @ Living



Line of Stair Clearance (Lower)



Detail shows assumptions used for framing plan RO.
Framer may adjust to suit different head support methods

Top of Carriage (B)

Scale: 1" = 1'-0"

Your use of these drawings constitutes an acceptance of responsibility as outlined in "Dear Code Officer" on the first page of these drawings, and on our web site:
<http://www.artformhomeplans.com/TermsConditions.a5w>

If you have any concerns or questions, please feel free to contact us. We are happy to clarify matters that fall within our scope, as listed on the first page. We can also often provide affordable support for issues that are your responsibility, such as energy design/calcs, or additional detailing.


Artform Home Plans
AFHP Design # 414,144
© 2008-2015 Wendy Welton 603.431.9559

Strawberry Ranch
1 Sunningdale
Somersworth, NH

1/4"=1'-0" unless noted otherwise / Print @ 1:1
PDF created on: 10/26/2015, drawn by ACJ

5

Issued for
Construction




4- Cross Section @ Garage


Framers Check List

Confirm or review the following prior to framing:

- | | | | |
|-------|----------|------|--|
| _____ | Initials | Date | Checked |
| _____ | | | Framing Plans, floor plans, elevations & sections on-site & reviewed |
| _____ | | | Confirmed window brand and sizes, adjusted RO's |
| _____ | | | Confirmed kitchen sink location & assoc. window |
| _____ | | | Confirmed duct chase sizes |
| _____ | | | Consult GC re: regional adjustments to framing member sizes per lumber yard calculations |
| _____ | | | If rafter size changed to accommodate snow load different, reviewed details, particularly where windows near roofs, for needed adjustments |
| _____ | | | Confirmed optional porch and/or deck sizes |




5- Cross Section @ Master Bedroom



First Floor Framing

Structure designed for
Snow Load of 60 psf



Built-up Beams:
Unless otherwise noted, connect multiple ply beams as follows:

- (2) 9 1/4" LVL:
 - Flush framed
 - (2) rows 5" TrussLock @ 16" oc, or
 - (2) rows SDS 1/4x6 @ 16" oc
 - Framed under (2) rows 10d nails @ 24" oc

- (2) 11 1/4" LVL:
 - Flush framed
 - (2) rows 3 3/8" TrussLock @ 19.2" oc, or
 - (2) rows SDS 1/4x3 1/2 @ 19.2" oc
 - Framed under (2) rows 10d nails @ 24" oc

- (2) 16" LVL or greater:
 - Flush framed
 - (2) rows 3 3/8" TrussLock @ 19.2" oc, or
 - (2) rows SDS 1/4x3 1/2 @ 19.2" oc
 - Framed under (2) rows 10d nails @ 24" oc

- (3) 9 1/4" LVL:
 - Flush framed
 - (2) rows 3 3/8" TrussLock @ 19.2" oc, or
 - (2) rows SDS 1/4x3 1/2 @ 19.2" oc
 - Framed under (2) rows 10d nails @ 24" oc

- (3) 11 1/4" LVL:
 - Flush framed
 - (2) rows 3 3/8" TrussLock @ 16" oc, or
 - (2) rows SDS 1/4x3 1/2 @ 16" oc
 - Framed under (2) rows 10d nails @ 24" oc

- (3) 16" LVL or greater:
 - Flush framed
 - (3) rows 3 3/8" TrussLock @ 16" oc, or
 - (3) rows SDS 1/4x3 1/2 @ 16" oc
 - Framed under (2) rows 10d nails @ 24" oc

- (4) 9 1/4" LVL:
 - Flush framed
 - (2) rows 5" TrussLock @ 16" oc, or
 - (2) rows SDS 1/4x6 @ 16" oc
 - Framed under (2) rows 10d nails @ 24" oc

- (4) 11 1/4" LVL:
 - Flush framed
 - (2) rows 5" TrussLock @ 16" oc, or
 - (2) rows SDS 1/4x6 @ 16" oc
 - Framed under (2) rows 10d nails @ 12" oc

- (4) 16" LVL or greater:
 - Flush framed
 - (3) rows 5" TrussLock @ 16" oc, or
 - (3) rows SDS 1/4x6 @ 16" oc
 - Framed under (2) rows 10d nails @ 12" oc

Beam Substitutions:
(2) 9 1/4" LVL may replace a double or triple 2x10 beam. No other substitutions are allowed. Conventional lumber beams MAY NOT be substituted for LVL beams by any "rule of thumb". Substitutions must be calculated by either Artform or a structural engineer. If calculated by a structural engineer, provide stamped plans and/or calculations.


We specify LVL beams as built-up members to allow framers to use existing stock. You may substitute single piece LVLs of equivalent overall size for built-up members, unless otherwise noted.

Built-up members MAY NOT replace single piece LVL's where specified.

Where a beam of 1 3/4" or less in width is specified as framed under, either brace at 48" or double member for lateral stability.







Your use of these drawings constitutes an acceptance of responsibility as outlined in "Dear Code Officer" on the first page of these drawings, and on our web site: <http://www.artformhomeplans.com/TermsConditions.a5w>

If you have any concerns or questions, please feel free to contact us. We are happy to clarify matters that fall within our scope, as listed on the first page. We can also often provide affordable support for issues that are your responsibility, such as energy design/calcs, or additional detailing.




Joist Attached to Rafter


used for:
Construction




Perspective View of Detail C




Alternate:
12" False Rake and a 6" Shed Dormer Rake



Roof Framing
Structure designed for
Snow Load of 60 psf




Valley Beam Attachment Options



Thermal and Moisture ONLY


1 1/2"=1'-0"

TABLE R602.10.4.1 CONTINUOUS SHEATHING METHODS				
METHOD	MATERIAL	MINIMUM THICKNESS	FIGURE	CONNECTION CRITERIA
CS-WSP	Wood structural panel	3/8"		6d common (2" x 0.113") nails at 6" spacing (panel edges) and at 12" spacing (intermediate supports) or 16 ga. x 1 1/4" staples at 3" spacing (panel edges) and 6" spacing (intermediate supports)



For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 pound force = 4.448 N.

FIGURE R602.10.3.4
METHOD PFG PORTAL FRAME AT GARAGE DOOR OPENINGS IN SEISMIC DESIGN CATEGORIES A, B AND C



For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 pound force = 4.448 N.

FIGURE R602.10.4.1.1
METHOD CS-PF: CONTINUOUS PORTAL FRAME PANEL CONSTRUCTION

174

2009 INTERNATIONAL RESIDENTIAL CODE®

Shear Wall Details

Not to Scale

Notes:

- See plans for locations where shear panels are required.
- Details shown here are for one method and for typical conditions. An alternate shear method allowed per code or approved by the code officer may be substituted.
- If the method at left is used at Garages where width of panel is 20" or more, wall height may be 10 ft as shown in detail at left. Where panel width is 18"-20", wall height may be 9 ft. Where panel is 16"-18", wall height may be 8 ft. Where panel is less, consult architect for additional design.
- If the method at left is used, increase foundation wall height at front and for 2 ft along wall returns as required to meet maximum wood stud wall heights, and extend sheathing and siding in front of wall to achieve desired aesthetics. Untreated wood may not be in direct contact with concrete - use treated wood or provide a barrier, such as a rubber membrane or felt paper.
- Note that if sheathing is to be used as wall bracing all vertical joints in required braced wall panels must be blocked. [2009 IRC section R602.1.8]

Your use of these drawings constitutes an acceptance of responsibility as outlined in "Dear Code Officer" on the first page of these drawings, and on our web site: <http://www.artformhomeplans.com/TermsConditions.a5w>

If you have any concerns or questions, please feel free to contact us. We are happy to clarify matters that fall within our scope, as listed on the first page. We can also often provide affordable support for issues that are your responsibility, such as energy design/calcs, or additional detailing.

Artform Home Plans
AFHP Design # 414.144
© 2008-2015 Wendy Welton 603.431.9559

Strawberry Ranch
1 Sunningdale
Somersworth, NH

1/4"=1'-0" unless noted otherwise / Print @ 1:1
PDF created on: 10/26/2015, drawn by ACJ

TM 1

Issued for
Construction